



Craven County Bridge

Division:
Bridge and Heavy Construction

Location:
Craven County, NC

Client:
NCDOT

Service Period:
2021-2023

- Services Provided:**
- Bridge Construction
 - Clearing
 - Grading
 - Paving
 - Storm Drain,
 - Utility Relocation

- Project Size:**
- 2 bridge replacements
 - 3,500 LF of waterline
 - 700 LF of sheet pile retaining wall

SCI Delivers Bridge Replacements Ahead of Schedule

The North Carolina Department of Transportation (NCDOT) awarded this bridge replacement project to Sanford Contractors (SCI). The Team was tasked with two bridge replacements, 3,500 LF of waterline relocation, and 700 LF of sheet pile retaining wall, all constructed on new alignment while maintaining traffic on the adjacent roadway.



Bridge 138 and Bridge 139 in Craven County, NC, were in poor condition and nearing the end of their service life. With only a four-month window to accomplish “in-water” work, scheduling and material acquisitions were essential to the success of this project. Installing four temporary work bridges coupled with the installation of eight pipe pile bents for the bridge foundations proved challenging, but SCI’s team members accepted the task and completed a quality project.

Teamwork, planning, and cooperation from Mother Nature enabled the SCI team to deliver this project 13 months ahead of schedule.

